





# Open19 Workshop



### **Brad Peterson**



### **Sergiy Zhuk**

Staff Engineer, Data Center LinkedIn

Director, Hardware Engineering LinkedIn








# The Open19 Project




# **Open19 Project Goals**

- Create an open standard that can fit any 19" Rack environment for server, storage, and networking
- Create a solution that will have applicability for large, medium, and small scale data centers




### Eco system with high adoption level



# **Platform Building Blocks**– Rack level

**Blind mate** 400w power cables

Blind mate 100G data cables







## **Brick Cage**





- Passive mechanical cage
- 12RU and 8RU options
- 2RU modularity
  - 4x Bricks
  - 2x Double High Half Width
  - 2x Double wide
  - 1x Double High
- Snap-on rear opening





### **Cabling system** Open19 Power Cables

### • 400W per server – 8/12 servers per cable

- **Open19 Data Cables**
- 100G Per server 8/12 servers per cable







## **Rack View**









# **Bricks Form Factors**



- Four brick form factors
  - Brick ( $\frac{1}{2}$  wide 1RU)
  - Double High Half Width (2RU)
  - Double Wide Brick (1RU)
  - Double High Brick (2RU)



- Linear power and data growth
- Self Sustained EMI & Safety & cooling
- 100G Blind Mate network



### Open. Together.

**Double High Double Wide Brick** 

# **Open19 Switch**





- Dual switch: Data Path & Management (OOB)
  - 50G per server data path
  - 1G per server management (optional)
  - Console port per server (optional)
- 12v input (no power supplies)
- Up to 8x100G uplinks
- **Broadwell-DE CPU with BMC**
- LinkedIn white box design






# **Open19 Power shelf**

- 1RU, 19.2Kw (6x3.2Kw)
- Management via GE port
- Full AC and DC range
- Per server protection and monitoring
- Fully redundant A/B inputs
- Multi-Source for the shelf and modules









# **Future Developments for Open19**

- Open orchestration & management software
- Different cage form factors  $\bullet$
- New "server" models
- Automated data center deployment model
- Optical snap-on data cabling  $\bullet$
- Liquid cooling integration ullet
- Automated data center








# **Open19 Project Status**



# **Open19 live @ Linkedin**







# **Build Open19 by the Numbers**

- Infra 40-60 Minutes per rack
- 96 servers 10 minutes per rack
- Total ~100 minutes per rack (2 technicians)
- 2 days for a full cluster 1536 Servers







# **Open19 Benefits**

- Much faster deployment
- 40% CapEx cost savings
- Up to 4x the space density
- Up to 50% the power savings





# **Summary**

- Open19 is about defining a common form factor
- Open19 is about community collaboration  $\bullet$
- Open19 technology is production since Q3 2018
- Open19 is is based on a common open infra Cages/Power/Cable/Network
- Open19 is about shared form factor into a variety of servers and storage solutions





