

Building and Operating an **OCP Data Center at Small** Scale

Dr Jon Summers, Research Leader, Research Institute of Sweden (RISE)





OCP CASE STUDIES



Case Studies



Open. Together.











Agenda

- What is the BodenTypeDC project? •
- The design of an OCP style of data center at small scale.
- The opensource software monitoring chain.
- Operational results. •
- Live and (hopefully) interactive demonstration of • remote operation of the small scale OCP data center.









Open. Together.

BodenType Data Center H2020 Project

- The BodenType Data Center (BTDC) project is funded by the EU
- To pilot a cost and energy efficient sub 1MW prototype data center.









GA 768875

Three Data Center PODs

Designed for 500kW of Information Technology.

Test POD 1 has legacy Open Compute Project IT – Windmill.

POD 2 and 3 are designed for HPC/GPU test partners for a target 350kW.

This project has received funding from the European Union's Horizon **2020 Research and Innovation** programme under grant agreement No 768875.

Visit https://bodentypeDC.eu











BodenType DC H2020 Project

- Rapid growth in data center energy consumption in Europe from 86TWh in 2013 to an anticipated 104TWh in 2020 (reference P.Bertoldi from the EU JRC).
- Aim of BodenType DC project to create a pilot data center that is cost and energy efficient with minimal environmental impact – to demonstrate this requires a comprehensive monitoring and measurement tool.
- Efficiency is focussed on reducing power losses no UPS, reducing cooling power consumption – using direct air (measured comparison with other methods) and better utilization of the IT systems – workload deployment and management.

P. Bertoldi, The European Programme for Energy Efficiency in Data Centres: The Code of Conduct, EU DG JRC, Institute for Energy and Transport, 2016.





Visit https://bodentypeDC.eu

Project partners are:





BodenType DC H2020 Project

Rapid growth in data center energy consumptionent Europe from 86TWh in 2013 to an anticipate afficient 104TWh in 2020 (reference P.Bertoldi for afficient JRC).
Aim of BodenType DC project note and the second state of the second

Bertoldi, The European Programme for Energy Efficiency in Data Centres: The Code of Conduct, EU DG JRC, Institute for Energy and Transport, 2016.





Visit https://bodentypeDC.eu

Project partners are:





The complete BTDC One Building and plan view of POD1











The complete BTDC One Building and plan view of POD1























Edgetic Reserved to the second second







Server wind tunnel



HEX

RADIAL FAN

TEMP and FLOW sensors

Set temperature with the HEX chilled water flowrate and wind tunnel FAN speed.

Air flowrate with the wind tunnel FAN – can pressurize the cold aisle as would happen in the contained cold aisle in the DC.

Upstream and downstream temperature measurements.

Can support between 1U and 4U of Information Technology.

Currently limited control over the air relative humidity.



Results with the OCP Windmill Server

• Wind tunnel results are captured using the same data center monitoring tools.



Uses the same opensource monitoring system as the data center.

The project uses many different workload generation approaches.

Note the variation of power consumption with server supply temperature - combination of increased fan power and current leakages.

Temperatures are in °C

Pressure drop was not kept constant for the different inlet temperatures.



RI SE

Relationship between the delta T and power consumption of the IT.

OCP Server Power vs. $\Delta T (\Delta P=0, Ti=20^{\circ}C)$



Power/blade [W]



x 480 servers

The cooling strategy is to set a delta T on the cooling systems to match idle power.

When IT power increases the coolers will speed up the supply and extract fans to maintain the supply temperature and to try and maintain the return temperature based on the idle delta T.

This will result in pressurisation of the contained cold aisle.

A more efficient strategy is to allow the return temperature to match the exhaust temperature from the servers.

 Wind tunnel HEX kept inlet temperature constant and the FAN kept the server pressure drop to 0.













Wind tunnel to determine ΔT , fixed CPU temp, regulate air consumption on pressure.



Innovation around thermal management POD 1 – Cooling Units set T_{supply} and T_{return}



Wind tunnel to determine ΔT , fixed CPU temp, regulate air consumption on pressure.





GA 768875

nausted Phase 1

Cooler responds immediately to IT power consumption. Phase 2

Fix the temperature of the CPUs via control of fans irrespective of workload. Phase 3 (TODO) Fan response to local distributed workload, pressure and more.

Exhausted









Cooling system strategy

Supply Fan Settings

	Home	Global	0 kVV	12 %	15.0 C
-0-	Settings	Water 🙀	10 kVV	12 %	12.0 C
		Suppry 🖍	20 kVV	20 %	12.0 C
	Status	Control	30 kW	35 %	12.0 C
	Alarms		40 kW	37 %	12.0 C
[\$\$<	Graphs		50 kVV	39 %	12.0 C
$\overline{\mathbf{A}}$	linfo	Power	60 kW	40 %	12.0 C
	Log In	Draw (W) 8592	70 kW	45 %	12.0 C
	12	Power	Fan		Delta
	BODEN	Draw (kW)	Speed (%	6)	т (°С)
•	NE	8	12		120
22/07/201	9 11:07 VNC U	Jser Connected CPU 080%	PLC HMIA HMI	B HMIC	HMID ROOM



GA 768875



Pod 1 Master

12.0 C

Defaults

ECT10800 H2020 Pod HMI 3.5 AB







Cooling system strategy





















Varying CPU utilisation on servers using synthetic and application specific workloads.





GA 768875





RI. SE

Results in the following profile of power consumption







GA 768875

Changes in IT workloads causes large variation in IT power consumption

The facility power consumption shows only small changes

Instantaneuous PUE and 30 day average PUE remains fairly constant because of the communication between IT and cooling controller

Visit https://bodentypeDC.eu







Supply and return temperatures



OCP Server Power vs. ΔT ($\Delta P=0$, Ti=20°C)



dT Current: 12.31 °C





GA 768875

The hot aisle temperatures varies with varying IT workload

The supply temperature to the cold aisle remain at desired setpoint

The delta T across the IT follows the expected values based on the relationship studied in the wind tunnel

Visit https://bodentypeDC.eu











Differential pressure and cooling units fan speeds





GA 768875



RI. SE

Heat sinks in OCP Servers



LOCALLY DEVELOPED FAN CONTROLLER

Aim to achieve lower flow rates and higher delta temperature across the Windmill servers.

Flowrate control is also achieved by the use of some locally developed fan controller cards.

Run to a fixed CPU temperature on all servers despite workload or calculate flowrate through each server and provide this information to the fresh air cooling system.

Replaced aluminium heat sinks containing embedded heat pipes with copper heat sinks.



Phase 2 of the holistic cooling – OCP servers





Extract setpoint Current: 34.00 °C
 Supply setpoint Current: 22.00 °C



OCP Server Power vs. ΔT ($\Delta P=0$, Ti=20°C)

Phase 2 of the holistic cooling – cooling systems

	Pod 1 - Mas Ambient Temp: A 13.0°C RH: A 94.5%	E 12.8°C B 95.4% Weather Station RH: **.*% Dew Point: 9.9*
Home Constructions	Cooler A Auto.Remote Ventilation Fan Speed 30% Supply 16.3°C S.P 15.0°C Att. 0%	Cooler B Auto.Remote Ventilation Auto Fan Speed 30% Supply 16.7°C S.P 15.0°C Sup Att. 0%
Status Status Alarms Graphs	Cooler Power 0448 W IT Power 040.8 kW PUE 1.010	Cold Aisle Temp:A 16.3°C B 17.6° RH:A 74.3% B 67.29 Server Average Fan Speed 375 rp Server Average Delta T 14.35 C Cold Aisle Pressure: A2Pa
i Info	Extract A	Hot Aisle Temp: A 28.1*C B 27.6*C RH: A 36.0% B 33.5*
BODEM	Fan Speed 0% Extract 29.2°C Extract RH 34%	Fan Speed 0% Extract 28.8°C Extract RH 34%





Phase 2 of the holistic cooling – cooling systems

		C	hip emp
Home	System	Rack 1	63.2C
Settings	Network	Rack 2 Rack 3 Rack 4	62.0C
D Status	PLC Data	Rack 5 Pack 6	58.8C
Alarms	Graph Data Handling	Rack 7 Rack 8	52.6C
Graphs	Averages Data	Rack 9 Rack 10	59.5C
i Info	Rack Data	Rack 11 Rack 12	56.2C
Log In		Average	58C
BODEN		Maximum	63C





Phase 2 of the holistic cooling – cooling systems





Live and interactive demonstration of the OCP POD1 operation

- Placeholder slide for around $\frac{5}{10}$ minutes of demonstration. (Needs an interent connection!)
- Show different workload deployment scenarios kubernetes versus loading OCP servers to their sweet spots for the environmental conditions at the time.
- Hope to show results of some Key Performance Metrics.
- Data will show power draw, temperature differences.

RUN DEMO









Call to action / ask of the OCP community

- the server fans? YES/NO
- consumption as well as fan metrics and data.
- servers.





• Should data center operators be trusted to take control of

Could there be open access to extract server fan energy

 Could the Open System Firmware allow greater access for server fan data and include control for synchronised control of the airflows between the coolers and the



Open. Together.



SUMMARY

- The project operates and monitors an experimental, but realistic test data center.
- Deployed a chain of opensource software to monitor the data center, IT utilisation and deterministic control of workload.
- Created a 140kW IT footprint using legacy OCP Windmill servers, with power, network and environmental and workload control.
- Piloting a data center cooled by direct air with a low cost humidification and an ambitious linking of facility and server fans.
- RISE can characterise thermal and power envelopes of servers using a uniquely developed server wind tunnel.
- Open Research Data Pilot will be available from the end of March 2020.

Visit https://bodentypeDC.eu

Thanks to RISE colleagues:

Jonas Gustafsson Daniel Olsson Jeffrey Sarkinen Magnus Nilsson-Mäki Filip Blylod Sebastian Fredriksson

This project has received funding from the European Union's Horizon 2020 Research and Innovation programme under grant agreement No 768875. Thanks to the other BodenType DC Project partners

H1 Systems Fraunhofer Institute of Optronics EcoCooling **Boden Business Agency**





Thanks also to

Edgetic











Open. Together.

OCP Regional Summit 26–27, September, 2019



